BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: **Reserve fund for emergency work in ward no.13** (Desilting of Secondary Drain & Construction of RCC Drain at Kalyananagara in 2nd cross near Karimariyamma Temple, Pipeline Road, in Ward no. 13, in Shettyhalli Sub-Division.)

Sl. No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Removing and resetting of Footpath slab. Complete as per specifications.	Sqm	95.58	97.52	Rupees Ninety Seven and Fifty Two Paise Only
2	Removing B.S.Slab of drain and stacking etc., Complete as per specifications.	Sqm	.251.10	49.18	Rupees Forty Nine and Eighteen Paise Only
3	Excavation and removal of silt or silt mixed with sand in slussy condition from cannel beg, including disposal of the same in soil bank ion cannel the embackment in layer as directed extc, complete with intial lead upto 50 mtr and all lift. Complete as per specifications.	Cum	330.00	107.00	Rupees One Hundred Seven Only
4	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods Complete as per specifications.	Cum	119.19	148.93	Rupees One Hundred Forty Eight and Ninety Three Paise Only
5	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specifications.	Cum	21.32	4413.84	Rupees Four Thousand Four Hundred Thirteen and Eighty Four Paise Only
6	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 340kgs, with with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, Complete as per specifications.	Cum	41.79	5535.32	Rupees Five Thousand Five Hundred Thirty Five and Thirty Two Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-2
KRIDL, BBMP, Bangalore

Executive Engineer

7	Pr ding T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specifications.	Qtls	26.73	7244.04	Rupees Seven Thousand Two Hundred Forty Four and Four Paise Only
8	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness,including attached pilasters,buttresses, plinth and string courses cost of all materials, labour Complete as per specifications.	Sqm	386.00	311.64	Rupees Three Hundred Eleven and Sixty Four Paise Only
9	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	173.10	1600.00	Rupees One Thousand Six Hundred Only
10	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 3 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading Complete as per specifications.	Cum	119.19	74.07	Rupees Seventy Four and Seven Paise Only

Note: The said work for sanctioned estimate cost Rs.10.00Lakhs (Rupees Ten Lakhs Only) (Incl.10%+1%KRIDL Charges + 1% Quality control tests Charges) based On "Approved SR Rates"

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, Bangalore

Executive Engineer,
Dasarahalli Division,